Sl. No.	Description of Item	Unit	Quantity	Rate in Rs.	Amount in Rs.
43	**Supplying and drawing 3 core flat PVC sheathed submersible pump cable manufactured with electrolytic grade copper with flexible copper with low resistance conductor confirming to table 3 class 5 of IS:8130-1984 and virgin grade PVC insulation and powder coating extruded PVC sheathed suitable for working voltage upto 1100Volts as per IS-694:1990 & confirming to GTP of GROUP-A. P. No. 12 / I No. 2.10.4(1) 3C x 6 Sqm mm KPWD Electrical SR 2014-15**	Mtr	**1530.00**	188.70	**288711.00**
t	Construction of RO Water Purifier Plant at Balaji Layout, Devinagar and BB Nagar in Ward No 08 Kodigehalli, Kodigehalli Sub Division		1530.00		
44	**Erection of pumpset including aligning and balancing with all necessary erection materials and labour including supply and erection of one pair supporting clamps, one borewell cap. Cable clips with bolts, nuts, valves guages etc., involoved in the job (Necessary GI pipe and specials with be supplied by the board at the site free of cost) (As per rate approved KUWS & DB for year 2008-09**	Nos	**3.00**	3000.00	**9000.00**
t	Construction of RO Water Purifier Plant at Balaji Layout, Devinagar and BB Nagar in Ward No 08 Kodigehalli, Kodigehalli Sub Division		3.00		
45	**Supplying and fixing 20"x20"x2.5" polished wood board made of not less than 15mm thick plank on both sides with planks made out of not more than 2 pieces and fixing the same to the wall using tapered inverted wooden plugs screws etc., P No. 44 / I No. 6.6.6 KPWD Electrical SR 2014-15**	Each	**3.00**	302.00	**906.00**
t	Construction of RO Water Purifier Plant at Balaji Layout, Devinagar and BB Nagar in Ward No 08 Kodigehalli, Kodigehalli Sub Division		3.00		
46	**Supplying of 1.1 KV LT UG cable having aluminum conductor PVC insulated, extruded inner sheathed, galvanized, steel strip (except 2CX10Sq.mm wire armoured) confirming to IS-3975:1990 (No. of Strip indicated in GTP) & extruded PVC outer sheathed armoured cable with specified IS-1554 Part-1:1988 & confirming to GTP of GROUP-A P No. 55/ I No. 7.4.4 4 core 16 Sqmm KPWD Electrical SR 2014-15**	Mtr	**90.00**	140.40	**12636.00**
t	Construction of RO Water Purifier Plant at Balaji Layout, Devinagar and BB Nagar in Ward No 08 Kodigehalli, Kodigehalli Sub Division		90.00		
47	**Labour charges for laying of 1.1 KV class UG cable in existing trench GI pipe / stoneware pipe / on wall / on pole as required.In existing trench/duct. P No. 61 / I No. 7.8.1 6Sqmm to 16 Sqmm) KPWD Electrical SR 2014-15**	Mtr	**90.00**	10.80	**972.00**
t	Construction of RO Water Purifier Plant at Balaji Layout, Devinagar and BB Nagar in Ward No 08 Kodigehalli, Kodigehalli Sub Division		90.00		

Consultants

Sl. No.	Description of Item	Unit	Quantity	Rate in Rs.	Amount in Rs.
48	**Digging of trench of 0.6m deep x 0.50 mtr wide refilling the trench to the required ground level and consolidating etc., complete.(As per Civil SR KSRB I-2, P-7) P No. 61 / I. No. 7.9.3 KPWD Electrical SR 2014-15**	Mtr	**75.00**	85.00	**6375.00**
t	Construction of RO Water Purifier Plant at Balaji Layout, Devinagar and BB Nagar in Ward No 08 Kodigehalli, Kodigehalli Sub Division		75.00		
49	**Supplying and fixing of class A (medium duty) GI pipe of wall thickness not less than 3.25mm on pole/wall/drain crossing with necessary clamping arrangements for UG cable of 1.1 KV P. No. 62 / I No. 7.12.1 KPWD Electrical SR 2014-15 - 40mm dia GI pipe**	Mtr	**12.00**	345.00	**4140.00**
t	Construction of RO Water Purifier Plant at Balaji Layout, Devinagar and BB Nagar in Ward No 08 Kodigehalli, Kodigehalli Sub Division		12.00		
50	**Supplying and fixing L.T. cast Iron pot heads suitable for 1.1 KV class UG cable filled with necessary bitumen/insulating compound complete with terminals, clamps, bolts, nuts and washers etc., P. No. 62 / I.No. 7.13.2 KPWD Electrical SR 2014-15 - 16Sqmm**	No	**3.00**	280.00	**840.00**
t	Construction of RO Water Purifier Plant at Balaji Layout, Devinagar and BB Nagar in Ward No 08 Kodigehalli, Kodigehalli Sub Division		3.00		
51	**Supplying, fixing, wiring, earth electrode for grounding conduits, I.C. cutouts and other equipment's on the meter board using 40mm dia 2.90mm thick GI pipe 2.5 mtr long buried in a pit ... The pit should be filled with equal proportion of salt and charcoal 150mm all-round the pipe to complete depth. The connection from the pipe to the conduit etc., is to be established through GI wire of size as per ISI specification 7.3.3. of IS 732 using 12mm dia bolts, nuts, washers and check nuts etc., the pipe shall have 16 through holes of 122 mm dia, (P No. 55, I No. 7.1) KPWD Electrical SR 2014-15**	No	**3.00**	2727.00	**8181.00**
t	Construction of RO Water Purifier Plant at Balaji Layout, Devinagar and BB Nagar in Ward No 08 Kodigehalli, Kodigehalli Sub Division		3.00		
52	**Supplying & fixing of Porcelain fuse channel with cut out on existing wooden/panel using necessary nuts, bolts and washers.P No. 44 / I No. 6.7.2 KPWD Electrical SR 2014-15 - 32 Amps**	No	**18.00**	180.00	**3240.00**
t	Construction of RO Water Purifier Plant at Balaji Layout, Devinagar and BB Nagar in Ward No 08 Kodigehalli, Kodigehalli Sub Division		18.00		
53	**KSRB 13-7.1-4: Providing and fixing in position 50mm nominal bore gun metal non-return valve horizontal type of approved make including cost of all materials, labour and HOM of equipments with all leads complete as per specifications NO KBS 13.2.16 / 13.13 Page No. 93 Item No. 13.55 / PWD SR 2016-17**	No	**3.00**	1615.68	**4847.04**
t	Construction of RO Water Purifier Plant at Balaji Layout, Devinagar and BB Nagar in Ward No 08 Kodigehalli, Kodigehalli Sub Division		3.00		

Sl. No.	Description of Item	Unit	Quantity	Rate in Rs.	Amount in Rs.
54	**Providing NP/CP waste unions conforming to ISI specifications and fixing them in position as per directions including cost of materials, fixtures and conveyance to work spot etc., complete. P. No. 95 / I. No. 13.81.3 PWD SR 2016-7**	No	**3.00**	232.20	**696.60**
t	Construction of RO Water Purifier Plant at Balaji Layout, Devinagar and BB Nagar in Ward No 08 Kodigehalli, Kodigehalli Sub Division		3.00		
55	**Supplying and fixing 50mm dia GI X nipple with ISI mark with all lead and lift loading unloading and labour charges etc complete**	No	**12.00**	80.00	**960.00**
t	Construction of RO Water Purifier Plant at Balaji Layout, Devinagar and BB Nagar in Ward No 08 Kodigehalli, Kodigehalli Sub Division		12.00		
56	**Supplying shunt capaitors conforming to IS 2834, 3phase 400/440 volts grade for power factor improvement of rotating machinery, Capacitor in KVAR rating Nos. 2KVAR capacity with all lead and lift =, loading, unloading and labour charges etc complete as per specifications**	No	**3.00**	350.00	**1050.00**
t	Construction of RO Water Purifier Plant at Balaji Layout, Devinagar and BB Nagar in Ward No 08 Kodigehalli, Kodigehalli Sub Division		3.00		
57	**Supplying and fixing miniature circuit breakers on existing MCB distribution boards using necessary fixing materials and 'C' Type curve, indicator ON/OFF, energy cross-3 with Short circuit breaking capacity of 10K and complete wiring as required confirming to IEC 60898. 5-32Amps TPN P No. 47 / I No.6.16.5 KPWD SR 2014-15**	No	**3.00**	1547.00	**4641.00**
t	Construction of RO Water Purifier Plant at Balaji Layout, Devinagar and BB Nagar in Ward No 08 Kodigehalli, Kodigehalli Sub Division		3.00		
58	**Fabricating supplying and mounting MS box made out ... SWG suitable for floor / wall mounting, fully weather proof with provision for better heat dissipation, provided with hinged front cover, equipped with tamper proof locking arrangements, with suitable size clamps with necessary cable entry pipe with gland and box should be finished with 2 coats of red oxide primer paint and finally finished with approved colour enameled metal paint etc., complete P.No. 49, I. No. 6.40.2 KPWD Electrical SR 2014-15 - 16SWG**	No	**65700.00**	0.33	**21681.00**
t	Construction of RO Water Purifier Plant at Balaji Layout, Devinagar and BB Nagar in Ward No 08 Kodigehalli, Kodigehalli Sub Division		65700.00		

Sl. No.	Description of Item	Unit	Quantity	Rate in Rs.	Amount in Rs.
59	**Supplying and delivery at site brand new star / Essen/ Lotus/Sun-shines/Adarsh/ GK Controls best indigenous make combined energy meter - cum-control panel board unit of size 600x450 x200 mm minimum mechanically strong vermin and water proof. The unit shall have two detachable doors suitable for operation on 3 ph, 50Hz, 380/440 volts, A.C supply with spring loaded latch, locking device with a key ribs should be provided inside the door, canopy apron and louvers ventilators shall be provided. the combined energy meter cum- control panel board unit suitable for operation. The panel board shall be fabricated on single unit in the above components for suitable pumpset. 12.5HP to 15 HP Star Delta Starter SERDED Rate**	No	**3.00**	11000.00	**33000.00**
t	Construction of RO Water Purifier Plant at Balaji Layout, Devinagar and BB Nagar in Ward No 08 Kodigehalli, Kodigehalli Sub Division		3.00		
60	**Earthwork excavation for pipeline trenches including deporiting or bank up to a lead of 50 mtrs including shiriry and statting danger lighting and using site rails and boming poles at every 100 mtrs wherever necessary as directed in th following strructure manhole. Page No. 01/ Item No.1.2.2 / PRED SR 2012-13 Hard Soil**	Cum	**81.00**	188.00	**15228.00**
t	Construction of RO Water Purifier Plant at Balaji Layout, Devinagar and BB Nagar in Ward No 08 Kodigehalli, Kodigehalli Sub Division		81.00		
61	**Providing and instalation at site of works P.V.C.Pipes including cost of pipes and specials and incluidng lowring into trenches, laying true to line, level and perfect linking at joints, leak proof including jointing encasing the pipe alround to a depth Not less than 15cm with grave or selected earth avalabile from the execavation Etc., Page No.15 item No.3.4.2 b PRED SR 2012-13. - 75 mm dia 6 KSC PVC pipe**	Rmtr	**180.00**	157.00	**28260.00**
t	Construction of RO Water Purifier Plant at Balaji Layout, Devinagar and BB Nagar in Ward No 08 Kodigehalli, Kodigehalli Sub Division		180.00		
62	**Refilling the basement and pipeline treanches with secleted available earthe for trench excavation including authority condition in layers from thedi including disponsary of the sunplus earth with a heavy 200 mtrs Page No. 3 / Item No. 1.6 / PRED SR 2012-13**	Cum	**81.00**	61.00	**4941.00**
t	Construction of RO Water Purifier Plant at Balaji Layout, Devinagar and BB Nagar in Ward No 08 Kodigehalli, Kodigehalli Sub Division		81.00		
63	**KSRB 13.6.3-6 : Providing and fixing in position brass gate valve with C.I wheel of approved quality (screwed end) 50mm nominal bore including cost of all materials, labour and HOM of equipments with all leads complete as per specifications. Specification No. KBS 13.2.6/13.3 P. 92 / I.13.37 PWD SR - 2016-17**	Each	**6.00**	2216.16	**13296.96**

Sl. No.	Description of Item	Unit	Quantity	Rate in Rs.	Amount in Rs.
t	Construction of RO Water Purifier Plant at Balaji Layout, Devinagar and BB Nagar in Ward No 08 Kodigehalli, Kodigehalli Sub Division		6.00		
64	**KSRB 2-2.2 : Earth work excavation for foundation of buildings, culverts water supply, sanitary line and electrical conduits either in pits or in trenches 1.5m and above in width, in Hard soil not exceeding 1.5m, in depth including dressing the bottom and sides of pits and trenches, stacking the excavated soil clear from edges of excavation with lead upto 50m, after breaking of clods complete as per specifications, specification, No, KBS 2.1(a) / 2.3.5, Page No. 5 / Item No. 2.3/ PWD SR 2016-17**	Cum	**118.04**	204.12	**24094.32**
t	Construction of RO Water Purifier Plant at Balaji Layout, Devinagar and BB Nagar in Ward No 08 Kodigehalli, Kodigehalli Sub Division		72.14		
u	Construction of Bangalore One Centre Buliding at Balaji Layout and Kodigehalli Village in Ward No 08 Kodigehalli, Kodigehalli Sub Division		45.90		
65	**KSRB 2.14-1: Extra for additional lift of 1.5m. or part thereof for excavation In loose / soft or hard soil including cost of materials, labour complete as per specifications. (Page no -7, item no - 2.21)**	Cum	**13.52**	218.16	**2949.52**
u	Construction of Bangalore One Centre Buliding at Balaji Layout and Kodigehalli Village in Ward No 08 Kodigehalli, Kodigehalli Sub Division		13.52		
66	**Providing and laying in position plain cement concrete of mix 1:3:6 with OPC cement @220kgs, with 40mm and down size graded granite metal coarse aggregates @ 0.892cum and fine aggregates @ 465 cum machine mixed, machine mixed,concrete laid in layers not exceeding 15 cms, thick well compacted, in foundation and plinth, including cost of all material, labour HOM Machinery curing complete as per specification,(Page. No. 12 Item No. 4.2**	Cum	**5.66**	5449.68	**30834.29**
u	Construction of Bangalore One Centre Buliding at Balaji Layout and Kodigehalli Village in Ward No 08 Kodigehalli, Kodigehalli Sub Division		5.66		
67	**KSRB 4-1.3 : Providing and laying in position plain cement concrete of mix 1:4:8 with OPC cement @ 180 kgs with 40mm and down size graded granite metal coarse aggregates @ 0.85cum and fine aggregares @ 0.57 cum machine mixed, concrete laid in layers not, exceeding 15cms, thick, well compacted, in foundation and plinth, including cost of all materials, labour, HOM of machinery, curing complete as per specifications. Specification No. KBS 4.1,4.2. No. 12/ Item No. 4.3/ PWD SR 2016-17**	Cum	**20.17**	5256.36	**106020.78**
t	Construction of RO Water Purifier Plant at Balaji Layout, Devinagar and BB Nagar in Ward No 08 Kodigehalli, Kodigehalli Sub Division		20.17		

Sl. No.	Description of Item	Unit	Quantity	Rate in Rs.	Amount in Rs.
68	**KSRB 5.2.3 : Providing and constructing granite / trap / basalt size stone masonry in foundation with cement mortar 1:6, stone hammerd dressed in courses not less than 20 cms high, bond stones at two m. apart in each course including cost of materials, labour, curing complete as per specifications.KBS 5.1.13 Page No. 23 / Item No. 5.6 / PWD SR 2016-17**	Cum	**16.74**	4521.96	**75697.61**
t	Construction of RO Water Purifier Plant at Balaji Layout, Devinagar and BB Nagar in Ward No 08 Kodigehalli, Kodigehalli Sub Division		16.74		
69	**KSRB 5.3-3 : Providing and constructing granite / trap / basalt size stone masonry in basement with cement mortar 1:6, edges of stones chistle dressed in courses not less than 15 cms high, bond stones at two m. apart in each course including cost of materials, labour, curing complete as per specifications.KBS 5-1.13 Page No. 23 / Item No. 5.9 / PWD SR 2015-16**	Cum	**14.81**	5405.40	**80053.97**
t	Construction of RO Water Purifier Plant at Balaji Layout, Devinagar and BB Nagar in Ward No 08 Kodigehalli, Kodigehalli Sub Division		14.81		
70	**KSRB 2.3 : Filling available excavated earth (excluding rock) in sides of foundations upto plinth in layers not exceeding 20 cms. in depth, compacting each deposited layer by ramming after watering with lead upto 50 m. and lift upto 1.5 m. including cost of all labour complete as per specifications. Specification No. KBS 2.9 (P.6/I.2.10) PWD SR 2016-17**	Cum	**134.35**	137.16	**18427.17**
t	Construction of RO Water Purifier Plant at Balaji Layout, Devinagar and BB Nagar in Ward No 08 Kodigehalli, Kodigehalli Sub Division		72.14		
u	Construction of Bangalore One Centre Buliding at Balaji Layout and Kodigehalli Village in Ward No 08 Kodigehalli, Kodigehalli Sub Division		62.21		
71	**KSRB 5-11 : Providing and constructing load bearing wall with solid concrete blocks of size 400x200x200 mm having block density not lessthan 1800 kg/m3 and having a minimum average compressive strength 5.00 N/mm2 confirming to IS 2185 (Part) : 2005 and constructed with CM 1:4 , as per IS 2572:2005 including cost of all materials, labour charegs, scaffolding, curing complete as per specifications. KBS No.5.4. Page No. 25 / Item No. 5.27 / PWD SR 2016-17**	Sqm	**347.13**	1011.96	**351281.67**
t	Construction of RO Water Purifier Plant at Balaji Layout, Devinagar and BB Nagar in Ward No 08 Kodigehalli, Kodigehalli Sub Division		166.56		
u	Construction of Bangalore One Centre Buliding at Balaji Layout and Kodigehalli Village in Ward No 08 Kodigehalli, Kodigehalli Sub Division		180.57		

Sl. No.	Description of Item	Unit	Quantity	Rate in Rs.	Amount in Rs.
72	**KSRB 4.2.2 : Providing and laying in position reinforced cement concrete of design mix M20 with OPC cement @ 320 kgs, with 20mm and down size graded granite metal, coarse aggregates @ 0.878 cum and fine aggregates @ 0.459 cum with superplastisiser @ 3lts confirming to IS 9103-1999 reaffirmed-2008 machine mixed, concrete laid in layers not exceeding 15cms thick, vibrated for all works in foundation plinth and ground floor level for roof slabs, staircase, lintels, retaining walls, walls (any thickness) including attached plasters, column, piers, abutments, pillars, posts, struts, buttresses, string or lacing courses, parapets, coping, bed blocks, anchor blocks, plain window cills, fillets etc, including cost of all materials, labour, HOM of machinery, curing, complete as per specifications. Specification No. KBS 4.1,4.6, No. 13/ Item No. 4.11/ PWD SR 2016-17**	Cum	**43.32**	6491.88	**281228.24**
t	Construction of RO Water Purifier Plant at Balaji Layout, Devinagar and BB Nagar in Ward No 08 Kodigehalli, Kodigehalli Sub Division		24.26		
u	Construction of Bangalore One Centre Buliding at Balaji Layout and Kodigehalli Village in Ward No 08 Kodigehalli, Kodigehalli Sub Division		19.06		
73	**KSRB 4.2.2 : Providing and laying in position reinforced cement concrete of design mix M20 with OPC cement @ 320 kgs, with 20mm and down size graded granite metal, coarse aggregates @ 0.878 cum and fine aggregates @ 0.459 cum with superplastisiser @ 3lts confirming to IS 9103-1999 reaffirmed-2008 machine mixed, concrete laid in layers not exceeding 15cms thick, vibrated for all works in foundation plinth and ground floor level for roof slabs, staircase, lintels, retaining walls, walls (any thickness) including attached plasters, column, piers, abutments, pillars, posts, struts, buttresses, string or lacing courses, parapets, coping, bed blocks, anchor blocks, plain window cills, fillets etc, including cost of all materials, labour, HOM of machinery, curing, complete as per specifications. Specification No. KBS 4.1,4.6, No. 13/ Item No. 4.11/ PWD SR 2016-17**	Cum	**20.78**	6650.64	**138177.02**
u	Construction of Bangalore One Centre Buliding at Balaji Layout and Kodigehalli Village in Ward No 08 Kodigehalli, Kodigehalli Sub Division		20.78		

Tejus Consultants

Sl. No.	Description of Item	Unit	Quantity	Rate in Rs.	Amount in Rs.
74	**KSRB 4.2.10 : Providing and laying in position reinforced cement concrete ofmix M20 with OPC cement @ 24kgs, with 12 mm and down size graded granite metal coarse aggregates @ 0.5175 cum and fine aggregates @ 0.345 cum with superplastisiser @ 0.225lts,machine mixed, well compacted for plain chajja of 7.5 cms. average thickness, upto ground floor lever, including cost of all materials, labour, HOM of machinery, curing, complete as per specification. Specification NO. KBS 4.1, 4.6 Page No. 14 / Item No. 4.19 / PWD SR 2016-17**	Sqm	**26.23**	492.48	**12917.75**
t	Construction of RO Water Purifier Plant at Balaji Layout, Devinagar and BB Nagar in Ward No 08 Kodigehalli, Kodigehalli Sub Division		6.07		
u	Construction of Bangalore One Centre Buliding at Balaji Layout and Kodigehalli Village in Ward No 08 Kodigehalli, Kodigehalli Sub Division		20.16		
75	**KSRB 4.9.1: Providing TMT steel reinforcement for R.C.C work including straightening, cutting, bending, hooking, placing in position, lapping and / or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per design (laps, hooks and wastage shall not be measured and paid) cost pf materials, labour, HOM of machinery complete as per specifications.Specification No. KBS 4.6.3 Page No. 17 / Item No. 4.46.2 / PWD SR 2016-17 - FE 500**	MT	**7.10**	75081.60	**532943.76**
t	Construction of RO Water Purifier Plant at Balaji Layout, Devinagar and BB Nagar in Ward No 08 Kodigehalli, Kodigehalli Sub Division		2.47		
u	Construction of Bangalore One Centre Buliding at Balaji Layout and Kodigehalli Village in Ward No 08 Kodigehalli, Kodigehalli Sub Division		4.63		
76	**KSRB 4-6.1 : Providing and removing centering, shuttering, strutting, propping etc., and removal of form work for foundations, footings, bases of columns for mass concrete including cost of all materials, labour complete as per specificaitons. Specification No. KBS 4.6.2(Page No : 15, item No : 4.28)**	Sqm	**34.56**	249.48	**8622.03**
u	Construction of Bangalore One Centre Buliding at Balaji Layout and Kodigehalli Village in Ward No 08 Kodigehalli, Kodigehalli Sub Division		34.56		
77	**KSRB 4-6.4 : Providing and removing centering, shuttering, strutting, propping etc., and removal of form work for vertical surface such as walls at any thickness, including attached pilasters, buttresses, plinth and string courses cost of all materials, labour complete as per specifications. Specification NO KBS 4.6.2 Page No. 15 / Item No. 4.31/ PWD SR 2016-17**	Sqm	**208.28**	316.44	**65908.12**
t	Construction of RO Water Purifier Plant at Balaji Layout, Devinagar and BB Nagar in Ward No 08 Kodigehalli, Kodigehalli Sub Division		176.24		
u	Construction of Bangalore One Centre Buliding at Balaji Layout and Kodigehalli Village in Ward No 08 Kodigehalli, Kodigehalli Sub Division		32.04		

Sl. No.	Description of Item	Unit	Quantity	Rate in Rs.	Amount in Rs.
78	**KSRB 4-6.5 : Providing and removing centering, shuttering, strutting, propping etc., for columns, pillars, post and struts, square / rectangular/ polygon in plan including cost of all materials, labour complete as per specifications. Specification No. KBS 4.6.2 (Page No : 16, item No : 4.32)**	Sqm	**86.24**	395.28	**34088.95**
u	Construction of Bangalore One Centre Buliding at Balaji Layout and Kodigehalli Village in Ward No 08 Kodigehalli, Kodigehalli Sub Division		86.24		
79	**KSRB 4-6.5 : Providing and removing centering, shuttering, strutting, propping etc., for columns, pillars, post and struts, square / rectangular/ polygon in plan including cost of all materials, labour complete as per specifications. Specification No. KBS 4.6.2 (Page No : 16, item No : 4.32)**	Sqm	**95.23**	338.04	**32191.55**
u	Construction of Bangalore One Centre Buliding at Balaji Layout and Kodigehalli Village in Ward No 08 Kodigehalli, Kodigehalli Sub Division		95.23		
80	**KSRB 4-6.7 :Providing and removing centering, shuttering, strutting, propping etc., and removal of form work for sides and soffits of beams, beam haunchings, cantilever girders, bressumers and lintels not exceeding 1m in depth including cost of all materials, labour complete as per specifications. Specification No. KBS 4.6.2(Page No : 16, item No : 4.34)**	Sqm	**80.46**	276.48	**22245.58**
u	Construction of Bangalore One Centre Buliding at Balaji Layout and Kodigehalli Village in Ward No 08 Kodigehalli, Kodigehalli Sub Division		80.46		
81	**KSRB 4-6.10 : Providing and removing centering, shuttering, strutting, propping etc., for chajjas, corbels etc., including edges including cost of all materials, labour complete as per specifications. Specification NO KBS 4.6.2 Page No. 16 / Item No. 4.37 / PWD SR 2016-17**	Sqm	**28.26**	291.60	**8240.62**
t	Construction of RO Water Purifier Plant at Balaji Layout, Devinagar and BB Nagar in Ward No 08 Kodigehalli, Kodigehalli Sub Division		8.10		
u	Construction of Bangalore One Centre Buliding at Balaji Layout and Kodigehalli Village in Ward No 08 Kodigehalli, Kodigehalli Sub Division		20.16		
82	**KSRB 15.3.13 : Providing 12mm thick cement plaster in single coat with cement mortar 1:3, to ceiling including rounding off corners wherever required smooth rendering, : Providing and removing scaffolding, including cost of materials, labour, curing complete as per specifications. Page No. 114 / Item No. 15.21 / PWD SR -2016-17**	Sqm	**141.96**	208.44	**29590.14**
t	Construction of RO Water Purifier Plant at Balaji Layout, Devinagar and BB Nagar in Ward No 08 Kodigehalli, Kodigehalli Sub Division		57.81		
u	Construction of Bangalore One Centre Buliding at Balaji Layout and Kodigehalli Village in Ward No 08 Kodigehalli, Kodigehalli Sub Division		84.15		

Sl. No.	Description of Item	Unit	Quantity	Rate in Rs.	Amount in Rs.
83	**KSRB 15.3.11 :Providing 20mm thick cement plaster in single coat with cement mortar 1:4, to stone masonry including rounding off corners wherever required smooth rendering, : Providing and removing scaffolding, including cost of materials, labour, curing complete as per specifications. Page No. 114 / Item No. 15.19 / PWD SR 2016-17 (Inside wall)**	Sqm	**132.36**	252.72	**33450.02**
t	Construction of RO Water Purifier Plant at Balaji Layout, Devinagar and BB Nagar in Ward No 08 Kodigehalli, Kodigehalli Sub Division		132.36		
84	**KSRB15-3.10 : Providing 20mm thick cement plaster in single coat with cement mortar 1:6, to stone masonry & concrete surface including rounding off corners wherever required smooth rendering, : Providing and removing scaffolding, including cost of materials, labour, curing complete as per specifications.(Page No :114, item No : 15.20)**	Sqm	**186.93**	224.64	**41991.96**
u	Construction of Bangalore One Centre Buliding at Balaji Layout and Kodigehalli Village in Ward No 08 Kodigehalli, Kodigehalli Sub Division		186.93		
85	**KSRB 15.3.2 Providing 12mm thick cement plaster in single coat with cement mortar 1:4, to brick masonry including rounding off corners wherever required smooth rendering, : Providing and removing scaffolding, including cost of materials, labour, curing complete as per specifications..(Page No.113, Item No.15.10)**	Sqm	**150.60**	178.20	**26836.92**
u	Construction of Bangalore One Centre Buliding at Balaji Layout and Kodigehalli Village in Ward No 08 Kodigehalli, Kodigehalli Sub Division		150.60		
86	**KSRB 15.10.2 Providing white washing for every one additional coat with lime of approved quality, to give an even shade including cost of materials, labour, complete as per specifications. (Page No. 115, Item No. 15.39)**	Sqm	**150.60**	4.32	**650.59**
u	Construction of Bangalore One Centre Buliding at Balaji Layout and Kodigehalli Village in Ward No 08 Kodigehalli, Kodigehalli Sub Division		150.60		
87	**KSRB 15.10.4 Providing white washing to ceiling and / or sloping roof surface with additional one coat with lime of approved quality, to give an even shade including cost of materials, labour, complete as per specifications.(Page No. 115, Item No. 15.41)**	Sqm	**84.15**	4.32	**363.53**
u	Construction of Bangalore One Centre Buliding at Balaji Layout and Kodigehalli Village in Ward No 08 Kodigehalli, Kodigehalli Sub Division		84.15		
88	**KSRB 15-7 : Providing lime rendering for plastering to wall and ceiling, including cost of materials, labour, curing complete as per specifications. (P. 115 / I. 15.33 PWD SR - 2016-17).**	Sqm	**190.17**	27.00	**5134.59**
t	Construction of RO Water Purifier Plant at Balaji Layout, Devinagar and BB Nagar in Ward No 08 Kodigehalli, Kodigehalli Sub Division		190.17		

Sl. No.	Description of Item	Unit	Quantity	Rate in Rs.	Amount in Rs.
89	**KSRB 15.3.9: Providing 18mm thick cement plaster in single coat with cement mortar 1:6, to brick masonry including rounding off corners wherever required smooth rendering, providing and removing scaffolding, including cost of materials, labour, curing complete as per specifications Page No. 114 / Item No. 15.17 / PWD SR 2016-17 (Out side Wall)**	Sqm	**172.68**	213.84	**36925.89**
t	Construction of RO Water Purifier Plant at Balaji Layout, Devinagar and BB Nagar in Ward No 08 Kodigehalli, Kodigehalli Sub Division		172.68		
90	**KSRB 15-14.1 : Providing and applying two coats with oil bound washable distemper of approved brand and shade on wall surface including priming coat with distemper primer after thoroughly brooming the surface free from mortar drops and other foregin matter including preparing the surface even and sand paper smooth, cost of materials, labours, complete as per specifications PWD SR 2016-17 (P.117 /I. 15.49.1)**	Sqm	**322.53**	76.68	**24731.60**
t	Construction of RO Water Purifier Plant at Balaji Layout, Devinagar and BB Nagar in Ward No 08 Kodigehalli, Kodigehalli Sub Division		322.53		
91	**KSRB 15-16.1: providing and finishing external walls in tow coats with water proof cement paint of approve brand and shade to give an even shade after thourghly brooming the surface to remove all dirt and losse powdered material, free from mortar dops and other foreign matter cost of materials, labours, complete as per specifications PWD SR 2016-17 (P. 118 / I. 15.53.2) with Primer**	Sqm	**359.61**	90.72	**32623.82**
t	Construction of RO Water Purifier Plant at Balaji Layout, Devinagar and BB Nagar in Ward No 08 Kodigehalli, Kodigehalli Sub Division		172.68		
u	Construction of Bangalore One Centre Buliding at Balaji Layout and Kodigehalli Village in Ward No 08 Kodigehalli, Kodigehalli Sub Division		186.93		
92	**Providing and applying two coats with Plastic emulsion paint of approved brand wall surface to a give an even approved shade after throuughly brushing the surface,free from mortar drops and other foreign matter, including priming , including preparing the surface even and sand paper smooth, cost of materials, labour, complete as per specifications,with primer. (Page No : 117, item No :15.51.2)For internal walls.**	Sqm	**150.60**	97.20	**14638.32**
u	Construction of Bangalore One Centre Buliding at Balaji Layout and Kodigehalli Village in Ward No 08 Kodigehalli, Kodigehalli Sub Division		150.60		

Tejus Consultants

Sl. No.	Description of Item	Unit	Quantity	Rate in Rs.	Amount in Rs.
93	**Providing and applying two coats with Plastic emulsion paint of approved brand wall surface to a give an even approved shade after throuughly brushing the surface,free from mortar drops and other foreign matter, including priming , including preparing the surface even and sand paper smooth, cost of materials, labour, complete as per specifications,with primer. (Page No : 117, item No :15.51.2)For internal walls Ceiling**	Sqm	**84.15**	101.52	**8542.91**
u	Construction of Bangalore One Centre Buliding at Balaji Layout and Kodigehalli Village in Ward No 08 Kodigehalli, Kodigehalli Sub Division		84.15		
94	**Providing vitrified tiles 60 x 60cms of approved make, shade and size for flooring laid on a bed of 12mm thick cement mortar 1:3 mix, flush pointing with white cement using colour pigment, including cost of materials, labour, curing complete as per specification. (Page No : 107, item No :14.45)**	Sqm	**50.00**	1200.96	**60048.00**
u	Construction of Bangalore One Centre Buliding at Balaji Layout and Kodigehalli Village in Ward No 08 Kodigehalli, Kodigehalli Sub Division		50.00		
95	**KSRB 14-17.2 : Providing skirting, dado, rises of steps with colour glazed tiles on 10mm thick cement plaster 1:3 and jointed with white cement slurry over rough plaster surface (excluding cost of rough plastered surface which should be measured and paid separately) using glazed tiles of approved make and size including cost of materials, labour, complete as per specifications. Specification No.KBS 14.16, 14.17 - Colour glazed tiles 30x60 cms 6mm thick with border of size 30 x 10 cms. (P.No.106, I.No. 14.41.2)**	Sqm	**5.02**	1602.72	**8045.65**
u	Construction of Bangalore One Centre Buliding at Balaji Layout and Kodigehalli Village in Ward No 08 Kodigehalli, Kodigehalli Sub Division		5.02		
96	**KSRB 9.4-2 : Providing Honne wood frames of doors, windows, clerestory windows, ventilators and other frames, wrought, framed or assembled including making plaster groves (excluding cost of cement concrete and side clamps), but including cost of materials, labour, HOM of machineries complete as per specifications. Specification No. KBS 9.33 (Page No : 51, item No :9.11)**	Cum	**0.23**	111083.40	**24993.77**
u	Construction of Bangalore One Centre Buliding at Balaji Layout and Kodigehalli Village in Ward No 08 Kodigehalli, Kodigehalli Sub Division		0.23		
97	**KSRB 9.5-2 : Providing and fixing in position fully panelled Honne wood shutters for doors, styles and rails of 40mm. thick with bottom and lock rails 180mm wide top rail and styles 100mm wide as per drawing and panels of 25mm thick including cost of materials, labour, HOM of machineries complete as per specifications. (excluding cost of fixtures) Specification No. KBS 9.34 (Page No : 51, item No :9.15)**	Sqm	**6.30**	5014.44	**31590.97**

Sl. No.	Description of Item	Unit	Quantity	Rate in Rs.	Amount in Rs.
u	Construction of Bangalore One Centre Buliding at Balaji Layout and Kodigehalli Village in Ward No 08 Kodigehalli, Kodigehalli Sub Division		6.30		
98	**KSRB 7.9:Providing and fixing .S.gill work for windows and ventilators using M.S.flats, or M.S. square rods, or combination of M.S.flats and square rods as per approved design, drawing including cutting steel sections and welding the same to required pattern with a coat of red lead primer, cost of materials, fixtures, labour and HOM of machinery complete as per specifications. Specification No. KBS 7.12 . (Page No : 32, item No :7.9)**	Kgs	**483.84**	84.24	**40758.68**
u	Construction of Bangalore One Centre Buliding at Balaji Layout and Kodigehalli Village in Ward No 08 Kodigehalli, Kodigehalli Sub Division		483.84		
99	**KSRB 7.10 : Providing and fixing in position aluminium windows and ventilators as per approved drawings with sliding shutters using double track window frame section of size 61.85x31.75mm. with 1.2mm thick, bottom section weight 0.695 kg/m, sides and top sections 1.3 mm. thick weight 0.659 kg/m; and shutter comprising top and bottom section of size 40mmx18mm, 1.25mm thick 0.417 kg./m; shutter outer side 40mmx18mm, 1.25mm.thick weight 0.417 kg/m, shutter interlock section 40mmx26.7mm, 1.1mm thick, weight 0.469 kg/m. the shutters mounted on nylon rollers with approved quality of fixtures such as aluminium handles tower bolts etc.; and providing and fixing 5.5mm. thick plain glass for shutters fitted with rubber beading aluminium sections including cutting to required length, joints mitred subdividing the frame tenonned and rivetted in the assembled frame stiffened with end clips at corners angles etc., and fixed to the walls, lintels, floor beams/cills as the case may be with necessary steel screws, raul plugs, or teak wood gatties including cutting masonry or concrete and making good the original surface using cement mortar, aluminium sections pretreated for removal of any Specification No. KBS using aluminium section anodized to 12 - 15 microns. (P.No. 301/ I. No. 7.10.1**	Sqm	**23.04**	4123.44	**95004.06**
u	Construction of Bangalore One Centre Buliding at Balaji Layout and Kodigehalli Village in Ward No 08 Kodigehalli, Kodigehalli Sub Division		23.04		
100	**KSRB 15-17.4 : Applying priming coat over new wood surface and / or wood based surface, after brushing with ready mix enamel priming paint including preparing the surface after thoroughly cleaning oil, grease, dirt and foreign matter, sand papering and knotting ready mix paint including cost of materials, labour, complete as per specifications.(Page. No. 118 Item No. 15.58)**	Sqm	**6.30**	33.48	**210.92**

Sl. No.	Description of Item	Unit	Quantity	Rate in Rs.	Amount in Rs.
u	Construction of Bangalore One Centre Buliding at Balaji Layout and Kodigehalli Village in Ward No 08 Kodigehalli, Kodigehalli Sub Division		6.30		
101	**Providing and applying painting two coats (excluding priming coat) on new wood surface and / or wood based surface with enamel paint to give an even shade, cleaning the surface of all dirt, dust and foreign matter, sand papering including cost of materials, labour, complete as per specifications.(Page. No. 118 Item No. 15.60.1)**	Sqm	**6.30**	90.72	**571.54**
u	Construction of Bangalore One Centre Buliding at Balaji Layout and Kodigehalli Village in Ward No 08 Kodigehalli, Kodigehalli Sub Division		6.30		
102	**KSRB 15-18.2 : Providing and applying enamel metal paint two coats (excluding priming coat) over new steel or other metal surface brushing to give an even shade after cleaning oil, grease, dirt and other foreign matter, including cost of materials, labour, complete as per specifications. Page No. 121 / Item No. 15.74 / PWD SR 2016-17**	Sqm	**105.16**	88.56	**9312.97**
t	Construction of RO Water Purifier Plant at Balaji Layout, Devinagar and BB Nagar in Ward No 08 Kodigehalli, Kodigehalli Sub Division		105.16		
103	**Providing and fixing Special make glazed Vitrified tiles (Granomite finis) of approved make, quality and colour of sized 6000x600x10mm thick fixed on existing flooring wit ha special roffe adhesive for flooring and skirting etc., complete including providing spears at required interval and removing stains etc., complete. Page No. 107 / Item No. 14.43 / PWD SR 2016-17**	Sqm	**123.29**	1285.20	**158452.31**
t	Construction of RO Water Purifier Plant at Balaji Layout, Devinagar and BB Nagar in Ward No 08 Kodigehalli, Kodigehalli Sub Division		123.29		
104	**Providing and laying/fixing cement base, precast pre polished cement concrete, designer tiles 25mm thick conforming to IS 1237 heavy duty tiles for flooring reads of steps of steps and landin, laid on a bed of 12mm thick cement mortar 1:3 mis finished with flush pointing using white cement, including cost of material,s including cutting, griding the edge ti half/ful rounf wherever requires labour, curing complete as per specification Page No. 109 / Item No. 14.62 / PWD SR 2016-17**	Sqm	**13.50**	1171.80	**15819.30**
t	Construction of RO Water Purifier Plant at Balaji Layout, Devinagar and BB Nagar in Ward No 08 Kodigehalli, Kodigehalli Sub Division		13.50		

Sl. No.	Description of Item	Unit	Quantity	Rate in Rs.	Amount in Rs.
105	**KSRB 7.7 : Providing and fixing in position in cement concrete 1:3:6 steel glazed windows and ventilators side hung/top hung fully openable as per approved drawings using Z angles of 25x33x3mm, weighing 1.419Kg/m both for outer and inner frames and central mullion section of size 25x46x3mm weighing 2.28Kg/m duly providing T section 19x19x3mm weighing 0.839 kg/m for glazing of windows not more than 34 cms. c to c including providing and fixing 4mm thick reeded glass with teakwood beading of required size, all steel section should confirm to I.S. 7452:1990, 4nos, of holdfasts of approved size section should be cut to length welded and electrically grinded subdividing frames of unit shall be tenonned and revetted into the frames electrically. All the steel surface shall be thoroughly cleaned free of rust and painted with one coat of anti-corosive paint and finishing with two coats of ready mix paint of approved colour and make including cost of materials, fixtures, labour and HOM of machinery complete as per specifications. Specification NO. KBS 7.12.1 / 7.12.2 / 7.12.3 / 7.12 Page No. 32 / Item No. 7.7/ PWD SR 2015-16**	Sqm	**3.24**	3812.40	**12352.18**
t	Construction of RO Water Purifier Plant at Balaji Layout, Devinagar and BB Nagar in Ward No 08 Kodigehalli, Kodigehalli Sub Division		3.24		
106	**KSRB: 7.5 Providing and fixing pull and push type rolling shutters of approved make out of 18 guage, 75mm wide cold rolled steel laths of convex corrugation, with side guides and bottom rail, with interlocking arrangements for steel laths by means of alternate clips, suspension shaft with High tension coil type springs two numbers, mounted on specially designed pipe shaft, with bracket plates, guide channels, ball bearing arrangements, for inside & outside locking with push & operations complete Including pulling hooks, 4nos handles wit hall fittings and accessories, painted with a coat of red lead paint (without top cover) cost of materials, labour, HOM of machinery complete as per specifications. Shutter size 3mx2.8m Specification NO. KBS 7.10 / 7.12 Page No. 31 / Item No. 7.5/ PWD SR 2015-16**	Sqm	**22.50**	3090.96	**69546.60**
t	Construction of RO Water Purifier Plant at Balaji Layout, Devinagar and BB Nagar in Ward No 08 Kodigehalli, Kodigehalli Sub Division		22.50		
107	**Providing revsrse osmosis system to cover 2000 Liters of High TDS water per hour with RAW WATER PUMP, SAND MEDIA FILTER, ACTIVATE CARBON FILTER, DOSING SYSTEM, MICRON FILTER, HIGH PRESSURE PUMP, RO membrane housing., RO MEMBRANES, RO CLEANSING SYSTEM, ELECTRICAL PANEL, INSTRUMENTATION, PH DOSING SYSTEM**	Nos	**3.00**	515000.00	**1545000.00**

Sl. No.	Description of Item	Unit	Quantity	Rate in Rs.	Amount in Rs.
t	Construction of RO Water Purifier Plant at Balaji Layout, Devinagar and BB Nagar in Ward No 08 Kodigehalli, Kodigehalli Sub Division		3.00		
108	**Supplying and wiring adopting loop system in existing PVC Conduit / casing capping using 1100V grade, COPPER conductor flexible multistrand FRLS PVC insulated, 2 X1.5Sq.mm Cable confirming to the GTP, with a 6Amps flush type SP control switch shall be fixed on the existing plastic sheet / gang box, the other end of the wires shall be terminated with sufficient loose length in a wood/PVC round block. complete for each outlet. GROUP A (Page No. 05, Item No.2.1 KPWD SR 2014-15 - b) Medium point above 3Mtr upto 6Mtr from tapping point to out let via switch**	Point	**6.00**	245.00	**1470.00**
t	Construction of RO Water Purifier Plant at Balaji Layout, Devinagar and BB Nagar in Ward No 08 Kodigehalli, Kodigehalli Sub Division		6.00		
109	**Supplying and wiring adopting loop system in existing PVC Conduit / casing capping using 1100V grade, COPPER conductor flexible multistrand FRLS PVC insulated, 2 X1.5Sq.mm Cable confirming to the GTP, with a 6Amps flush type SP control switch shall be fixed on the existing plastic sheet / gang box, the other end of the wires shall be terminated with sufficient loose length in a wood/PVC round block. complete for each outlet. GROUP A (Page No. 05, Item No.2.1 KPWD SR 2014-15 - c) Long point above 6Mtr upto 10Mtr from tapping point to out let via switch**	Point	**6.00**	363.00	**2178.00**
t	Construction of RO Water Purifier Plant at Balaji Layout, Devinagar and BB Nagar in Ward No 08 Kodigehalli, Kodigehalli Sub Division		6.00		
110	**Supplying and flush mounting teak wooden box without front plank, made of not less than 12mm thick wood, after due groove cutting, Finishing with necessary cement plastering complete (Page No. 03, Item No. 1.6) KPWD SR 2014-15 - (1.6.5) 4"x4"x3" (101x101x76mm)**	Each	**36.00**	68.00	**2448.00**
t	Construction of RO Water Purifier Plant at Balaji Layout, Devinagar and BB Nagar in Ward No 08 Kodigehalli, Kodigehalli Sub Division		36.00		
111	**Supplying and flush mounting teak wooden box without front plank, made of not less than 12mm thick wood, after due groove cutting, Finishing with necessary cement plastering complete (Page No. 03, Item No. 1.6) KPWD SR 2014-15 - (1.6.1) 12"x12"x3" (300x300x76mm)**	Each	**18.00**	116.00	**2088.00**
t	Construction of RO Water Purifier Plant at Balaji Layout, Devinagar and BB Nagar in Ward No 08 Kodigehalli, Kodigehalli Sub Division		18.00		
112	**Supplying and flush mounting teak wooden box without front plank, made of not less than 12mm thick wood, after due groove cutting, Finishing with necessary cement plastering complete (Page No. 03, Item No. 1.6) KPWD SR 2014-15 - (1.6.3)10"x7"x3" (254x178x76mm)**	Each	**18.00**	87.00	**1566.00**

Sl. No.	Description of Item	Unit	Quantity	Rate in Rs.	Amount in Rs.
t	Construction of RO Water Purifier Plant at Balaji Layout, Devinagar and BB Nagar in Ward No 08 Kodigehalli, Kodigehalli Sub Division		18.00		
113	**Supplying 4mm thick plastic sheet with necessary nitches for fixing switches, regulators etc., and fixing on existing wooden or metal box using N.F. screws. (Page No. 17, Item No. 3.9) KPWD SR 2014-15**	Sqcm	**19999.98**	0.25	**5000.00**
t	Construction of RO Water Purifier Plant at Balaji Layout, Devinagar and BB Nagar in Ward No 08 Kodigehalli, Kodigehalli Sub Division		19999.98		
114	**Extra for Groove cutting in brick wall/CC floor to the suitable depth for concealing of Conduit/GI pipe and plastering, finishing upto wall surface complete. upto 50mm conduit in brick wall (Page No. 03, Item No.1.7.1) KPWD SR 2014-15**	Mtr	**30.00**	21.00	**630.00**
t	Construction of RO Water Purifier Plant at Balaji Layout, Devinagar and BB Nagar in Ward No 08 Kodigehalli, Kodigehalli Sub Division		30.00		
115	**Supplying heavy gauge PVC Conduit Pipe 19/20 mm dia 2 mm thick with suitable size bends, metal junction boxes adhesive paste etc., by groove cutting in the wall and fixing by bracing U or J hooks and cement plastering up to the wall surface and run with 18 SWG GI fish wire run throughout the conduit wherever necessary. (Page No. 02, Item No. 1.3.1) KPWD SR 2014-15**	Mtr	**30.00**	56.00	**1680.00**
t	Construction of RO Water Purifier Plant at Balaji Layout, Devinagar and BB Nagar in Ward No 08 Kodigehalli, Kodigehalli Sub Division		30.00		
116	**Supplying and fixing PBBC/Bakelite straight or slant batten holder and wiring with 60w/230 volts lamps. (Page No. 20, Item No. 4.2) KPWD SR 2014-15**	Each	**6.00**	88.00	**528.00**
t	Construction of RO Water Purifier Plant at Balaji Layout, Devinagar and BB Nagar in Ward No 08 Kodigehalli, Kodigehalli Sub Division		6.00		
117	**Supplying patti type fluorescent tube light fitting of 2' - suitable for 14 watts fluorescent tube fitting, made out of M.S. Sheet and stove enameled with HF Electronic Ballast , locking type brass contact holders mounted on double fold type sheet base fully wired for use on 230 volts AC . Supply including T5 lamp. (Page No. 20, Item No. 4.5) KPWD SR 2014-15**	Each	**12.00**	591.00	**7092.00**
t	Construction of RO Water Purifier Plant at Balaji Layout, Devinagar and BB Nagar in Ward No 08 Kodigehalli, Kodigehalli Sub Division		12.00		
118	**Wiring for lighting/power circuit using one of FRLS PVC insulated 1100V grade, multistrand Copper with low conductor resistance single core wire in open or concealed system of wiring with specified IS-694:1990 & confirming to GTP of GROUP -A 1.5 sqmm (Page No. 06, Item No. 2.5.2) KPWD SR 2014-15**	Mtr	**15.00**	18.60	**279.00**
t	Construction of RO Water Purifier Plant at Balaji Layout, Devinagar and BB Nagar in Ward No 08 Kodigehalli, Kodigehalli Sub Division		15.00		

Sl. No.	Description of Item	Unit	Quantity	Rate in Rs.	Amount in Rs.
119	**Supplying and fixing cast Aluminum round or oblong type bulk head fitting with GI wire guard, glass cover with 60/100 watts 230V GLS lamp. (Page No. 20, Item No. 4.3) KPWD SR 2014-15**	Each	**12.00**	747.00	**8964.00**
t	Construction of RO Water Purifier Plant at Balaji Layout, Devinagar and BB Nagar in Ward No 08 Kodigehalli, Kodigehalli Sub Division		12.00		
120	**Supplying, fixing, wiring, earth electrode for grounding conduits, I.C. cutouts and other equipment's on the meter board using 40mm dia 2.90mm thick GI pipe 2.5 mtr long buried in a pit ... The pit should be filled with equal proportion of salt and charcoal 150mm all-round the pipe to complete depth. The connection from the pipe to the conduit etc., is to be established through GI wire of size as per ISI specification 7.3.3. of IS 732 using 12mm dia bolts, nuts, washers and check nuts etc., the pipe shall have 16 through holes of 122 mm dia (Page No. 55, Item No. 7.1) KPWD SR 2014-15**	No	**3.00**	2727.00	**8181.00**
t	Construction of RO Water Purifier Plant at Balaji Layout, Devinagar and BB Nagar in Ward No 08 Kodigehalli, Kodigehalli Sub Division		3.00		
				Construction Cost	**65819232.00**
121	**Add cost of Waste Plastic @ 8% of Bitumen weight**	Kgs	**34968.01**	27.00	**944136.00**
b	Improvements to Roads and Drains at Nethaji Layout in Ward No 7 Byatarayanpura, Kodigehalli Sub Divison.		1700.57		
c	Improvements to Roads and Drains at Kempapura Neeru Bhavi Muniyappa Layout in Ward No 7 Byatarayanpura, Kodigehalli Sub Divison.		534.67		
d	Improvements to Roads and Drains in Shabari Bakery Road at Kempapura in Ward No 7 Byatarayanpura, Kodigehalli Sub Divison.		812.16		
e	Improvements to Roads and Drains at Sneha nagar in Ward No 7 Byatarayanpura, Kodigehalli Sub Divison.		806.52		
f	Improvements to Roads and Drains at L&T Colony Near Amrutha Clinic in Ward No 7 Byatarayanpura, Kodigehalli Sub Divison.		1548.29		
g	Improvements to Roads and Drains near Chikka Muniyappa house at Amruthahalli in Ward No 7 Byatarayanpura, Kodigehalli Sub Divison.		872.85		
h	Improvements to Roads, Drains and Footpath from Sanjeevinianagar Ashwatha katte to Kodigehalli Main Road at Ravishanakar residency layout in Ward No 7 Byatarayanpura, Kodigehalli Sub Divison.		1394.21		
i	Improvements to Roads and Drains Adjacent to St. Johns School at Amruthahalli in Ward No 7 Byatarayanpura, Kodigehalli Sub Divison.		1874.51		
j	Improvements to Roads and Drains in front of Shriya Residency Near Old Police Station Amruthahalli in Ward No 7 Byatarayanpura, Kodigehalli Sub Divison.		1392.18		
l	Improvements to Roads and Drains in Amruthanagar B-Sector Near Amruthahalli New Police Station in Ward No 7 Byatarayanpura, Kodigehalli Sub Divison.		2021.83		
m	Improvements to Roads and Drains in Cross Roads of Dee Enclave Layout in Ward No 8 Kodigehalli, Kodigehalli Sub Divison.		2184.26		
n	Improvements to Roads and Drains Bhadrappa Layout in Ward No 8 Kodigehalli, Kodigehalli Sub Divison.		1595.67		
o	Improvements to Foothpaths at Sahakaranagar in Ward No 8 Kodigehalli, Kodigehalli Sub Divison.		1000.08		

Sl. No.	Description of Item	Unit	Quantity	Rate in Rs.	Amount in Rs.
p	Improvements to Foothpaths Roads and Footpath in Kannuramma temple main Road and Surrounding areas in Ward No 8 Kodigehalli, Kodigehalli Sub Divison.		4452.22		
q	Improvements to Foothpaths Roads and Footpath in Bhavi Muneshwara temple main Road and Surrounding areas in Ward No 8 Kodigehalli, Kodigehalli Sub Divison.		2974.99		
r	Improvements to Foothpaths Roads and Footpath to Lottegollahalli Main Road Near Jalageramma temple Road in Ward No 8 Kodigehalli, Kodigehalli Sub Divison.		2998.00		
s	Improvements to Foothpaths Roads and Footpath to Lottegollahalli Main Road Opp. RMV Cluster Appartments to Railway Gate near Vyasa School in Ward No 8 Kodigehalli, Kodigehalli Sub Divison.		6805.00		
122	**Cost towards Preparation of DPR LS**				**658192.00**
123	**Cost towards PMC / Third Party inspection LS**				**658192.00**
124	**Cost towards BESCOM deposite Charges for Borewell LS**				**34000.00**
125	**Cost towards BESCOM deposite Charges for RO Plant LS**				**25000.00**
126	**Cost towards Pole Shifting LS**				**200000.00**
127	**Cost towards Electrical Works**				**610013.09**
128	**Deposit Charges Towards BESCOM**				**5000000.00**
	Sub Total				**73948765.09**
129	**Utility Sgifting, Miscellaneous and rounding off LS**				**51234.91**
	Grand Total of the package				**74000000.00**

Total Cost of Package (In Words): Rupees Six Crore Ninety Lakh Only

Certificate.

1 The rates adopted based on the PWD SR, Bangalore circle for year 2016-17.
2 The provisions made in the estimate are necessary and essential.
3 The workspot was inspected and work is found to be necessary.
4 The area comes within the Bruhat Bangalore Mahanagara Palike limits.

For Tejus Consultants

Assistant Engineer
AE(W7)

Assistant Executive Engineer

Executive Engineer
Executive Engineer
Byatarayanapura Division
Yelahanka Zone, B.B.M.P.
Bangalore - 560 092

ADMINISTRATIVE APPROVAL

Accorded For Rs. 740.00
Head of A/c. P-3106
Div. Ref. No. 94/17-18 Date. 19/12/17
GO: UDD 640 MNY 2017 Dt: 11/12/17.

AE 19/12 EE(BTP) 19/12

Technical Sanction
Accorded For 740.00 lakh Rs.
Head of A/C. P3106
CER NO : 85 Dt:. 22 07 17

TA CE (YNK)